


KETTLE CREEK DRAINAGE BASIN OLD RANCH ROAD TRIBUTARY MASTER DEVELOPMENT DRAINAGE PLAN FULLY DEVELOPED CONDITION BASIN MAP AND MASTER PLAN



- KEYED NOTES**
- ANALYSIS POINT D24 REPRESENTS A DIRECT ADDITION OF THE HYDROGRAPHS AT ANALYSIS POINT D23 AND THE OUTLET HYDROGRAPH FROM THE CREEKSIDE ESTATES REGIONAL DETENTION FACILITY. IT DOES NOT REFLECT ANY OTHER FLOW IN KETTLE CREEK.
 - NATURAL CHANNEL IS PROPOSED TO BE ELIMINATED IN THIS AREA. STORM WATER TO BE CONVEYED IN A PROPOSED STORM DRAIN.
 - REMOVE EXISTING EMBANKMENT DOWN TO LEVEL OF PERMANENT POOL. PROTECT REMAINING EMBANKMENT IF PRUDENT TO DO SO IN ORDER TO PROTECT AGAINST EXCESSIVE EROSION.
 - NATURAL CHANNEL PROPOSED TO REMAIN UNIMPROVED IN THIS AREA.
 - DETENTION FACILITY OUTLET AND SPILLWAY ARE PROPOSED TO BE REVISED.

- GENERAL NOTES:**
- PROPOSED STORM DRAINS SHOWN ON THIS PLAN ARE ONLY INTENDED TO INDICATE GENERAL LOCATIONS AND APPROXIMATE SIZES OF FUTURE FACILITIES. ACTUAL STORM DRAIN SIZES AND LOCATIONS SHALL BE DETERMINED WITH MORE DETAILED ANALYSIS AT THE TIME OF DETAILED DESIGN OF THE FACILITIES. IT IS LIKELY THAT ADDITIONAL FACILITIES NOT SHOWN ON THIS PLAN WILL BE REQUIRED.
 - PROPOSED DETENTION FACILITIES SHOWN ON THIS PLAN ARE ONLY INTENDED TO INDICATE GENERAL LOCATIONS AND LAND AREA REQUIRED FOR THESE FACILITIES. ACTUAL LOCATIONS AND LAND AREA REQUIRED SHALL BE DETERMINED AT THE TIME OF DETAILED DESIGN OF THE FACILITIES.
 - EXCEPT AS OTHERWISE NOTED, THIS PLAN SHALL NOT MODIFY THE REQUIREMENTS OF PREVIOUSLY APPROVED MASTER DEVELOPMENT DRAINAGE PLANS AND FINAL DRAINAGE REPORTS.

**SUB-BASIN DATA SUMMARY
FULLY DEVELOPED CONDITION**

SUB BASIN I.D.	AREA (sq miles)	AREA (acres)	PERCENT IMPERVIOUS	CN	LAG (hours)	Q5 (cfs)	Q100 (cfs)
D1	0.085	24.7	33.0	67.5	0.383	17	72
D2	0.057	36.5	10.0	69.0	0.224	20	72
D3	0.028	16.8	33.3	75.0	0.267	13	40
D4	0.048	30.5	39.4	68.2	0.255	14	56
D5	0.030	18.1	30.4	74.5	0.238	10	47
D6	0.039	25.1	42.7	79.2	0.164	34	86
D7	0.071	45.5	46.8	79.8	0.173	62	157
D8	0.069	39.5	32.2	82.0	0.111	111	208
D9	0.022	13.9	41.1	77.0	0.251	14	37
D10	0.018	11.4	31.8	74.5	0.213	10	30
D11	0.027	17.4	68.0	83.0	0.307	7	27
D12	0.051	32.7	29.6	74.2	0.231	27	81
D13	0.021	13.3	34.5	74.6	0.280	10	31
D14	0.067	22.8	42.6	81.5	0.133	115	219
D15	0.023	15.0	36.7	78.0	0.158	19	49
D16	0.043	27.6	31.0	75.0	0.200	26	75
D17	0.025	38.8	41.0	72.5	0.197	31	98
D18	0.013	8.2	46.0	78.0	0.143	11	38
D19	0.019	6.5	32.8	76.5	0.117	10	25
D17A	0.011	6.7	60.9	99.0	0.120	21	56
D18	0.064	41.0	38.0	76.3	0.252	38	106
D19	0.024	15.1	40.0	80.9	0.122	25	59
D20	0.030	18.9	80.4	96.5	0.108	62	107
D21	0.041	28.4	62.5	84.0	0.137	56	117
D22	0.037	23.7	40.9	78.5	0.156	31	81
D23	0.005	3.5	56.7	88.0	0.110	8	15
D24	0.025	18.1	25.7	74.5	0.191	17	48
D25	0.017	10.8	33.2	82.0	0.156	16	42
D26	0.033	20.9	30.0	75.0	0.145	24	66
D27	0.008	5.0	46.5	80.0	0.143	8	19
D28	0.004	2.8	49.6	84.0	0.137	5	11
D29	0.018	11.6	37.8	78.2	0.146	15	40
D30	0.017	11.0	25.5	74.4	0.157	11	32
D31	0.007	4.5	40.0	78.5	0.146	6	16
D32	0.006	3.7	3.0	88.0	0.114	3	9
D33	0.036	23.3	10.4	70.2	0.138	18	59
D34	0.039	24.7	36.5	77.0	0.159	30	80
D35	0.059	24.7	40.0	78.0	0.161	32	85
D36	0.024	15.2	19.5	72.0	0.237	10	34
D37	0.011	6.8	93.1	99.0	0.124	23	40
TOTAL	1.269	812.0					

**ANALYSIS POINT DATA SUMMARY
FULLY DEVELOPED CONDITION**

ANALYSIS POINT	WATERSHED AREA (acres)	AREA (sq miles)	Q2 (cfs)	Q5 (cfs)	Q10 (cfs)	Q25 (cfs)	Q50 (cfs)	Q100 (cfs)	POINT DESCRIPTION
D1	90.8	0.14	11	31	48	79	102	127	TOTAL FLOW
DFA	107.4	0.17	17	44	66	105	134	165	TOTAL POND INFLOW
D2	132.5	0.21	30	64	91	151	176	219	TOTAL FLOW
DFB	49.6	0.08	13	30	44	68	85	103	TOTAL POND INFLOW
D3	227.6	0.36	73	148	198	254	291	330	TOTAL FLOW
DFC	287.1	0.42	139	237	311	405	465	524	TOTAL POND INFLOW
D4	278.5	0.44	47	64	73	85	102	127	TOTAL FLOW
D5	63.2	0.10	19	40	58	88	110	133	TOTAL FLOW
D6	106.1	0.17	90	141	178	238	280	323	TOTAL FLOW
D7	441.1	0.69	153	244	311	418	492	567	TOTAL FLOW
D7A	447.6	0.70	164	263	335	451	532	614	TOTAL FLOW
D8	502.3	0.78	191	310	398	538	637	739	TOTAL FLOW
D9	524.3	0.82	208	337	433	585	692	803	TOTAL FLOW
D10	56.5	0.09	15	29	32	44	54	65	TOTAL FLOW
D11	75.0	0.12	60	85	103	129	147	167	TOTAL FLOW
D12	625.7	0.98	299	470	596	796	935	1079	TOTAL POND INFLOW
D13	649.4	1.02	55	79	95	118	132	148	TOTAL FLOW
D14	652.9	1.02	58	84	101	127	144	161	TOTAL FLOW
DFD	669.0	1.05	66	100	123	159	184	208	TOTAL POND INFLOW
D15	31.7	0.05	23	41	56	77	92	108	TOTAL FLOW
D17	700.7	1.10	48	59	64	85	101	117	TOTAL FLOW
D18	705.7	1.10	49	59	72	98	116	135	TOTAL FLOW
D19	11.6	0.02	9	15	20	20	20	20	INTERCEPTED FLOW
D20	720.1	1.13	49	74	97	123	145	165	TOTAL FLOW
D21	731.1	1.14	49	84	111	146	171	196	TOTAL FLOW IN STORM DRAIN
D22	735.6	1.15	52	90	119	158	184	211	TOTAL FLOW
DFCS	739.3	1.15	53	83	123	164	192	221	TOTAL POND INFLOW
D23	80.4	0.13	9	80	153	307	440	544	TOTAL FLOW
D24	762.6	1.19	40	111	188	348	501	630	TOTAL FLOW FROM 'DFCS' & D23
DFG	49.4	0.08	33	60	81	115	138	162	TOTAL POND INFLOW

WATERSHED AREAS DO NOT REFLECT THE TRIBUTARY AREA REDUCTION DUE TO THE DIVERSION OF FLOW Q'S ARE COMPUTED BASED ON THE ACTUAL BASIN AREAS.

**** PEAK FLOW DIVERTED TO NATURAL CHANNEL DURING INFREQUENT RUNOFF EVENTS.**

- LEGEND**
- 5660 — EXISTING CONTOUR 10'
 - — — EXISTING CONTOUR 2'
 - - - - - DEVELOPED BASIN BOUNDARY
 - - - - - EXISTING STORM DRAIN
 - 48" — ESTIMATED STORM DRAIN SIZE PROPOSED STORM DRAIN
 - RBC — PROPOSED REINFORCED BOX CULVERT
 - DRAINAGE DIRECTION
 - D8 — BASIN IDENTIFIER
 - 39.5 — BASIN AREA (ACRES)
 - D4 — ANALYSIS POINT
 - ① — KEYED NOTE REFERENCE

DETENTION FACILITY DATA SUMMARY

DETENTION FACILITY I.D.	PEAK INFLOW (CFS)					PEAK OUTFLOW (CFS)					ESTIMATED PEAK STORAGE (ACRE-FEET)					
	Q2	Q5	Q10	Q25	Q50	Q2	Q5	Q10	Q25	Q50	V2	V5	V10	V25	V50	V100
A	17	44	66	105	134	165	17	38	45	54	60	85	0	0.1	1	4
B	13	30	44	68	85	103	13	30	39	47	52	57	0	0.0	0.1	0.4
C	139	237	311	405	465	524	45	60	66	75	81	86	3	7	10	18
E	298	470	596	796	935	1079	60	137	213	366	489	600	11	16	19	23
F	66	100	123	159	184	208	48	57	61	66	71	76	8	8	8	9
G	53	60	81	115	138	162	2	11	23	31	36	41	1	2	2	4
CREEKSIDE P.C. HIGH SCHOOL	83	93	123	164	192	221	37	55	61	73	79	90	3	5	5	5

UNTIL SUCH TIME AS DRAWINGS ARE APPROVED BY APPROPRIATE REVIEWING AGENCIES, JR ENGINEERING APPROVES THEIR USE ONLY FOR THE PURPOSES AUTHORIZED.

PREPARED FOR

JR ENGINEERING
A Subsidiary of Western
4910 Arroyo West Drive • Colorado Springs, CO 80907
719-533-2588 • Fax: 719-533-4603
www.jr-engineering.com

No.	DATE	BY	REVISION
1	10/2002	VSF	REVISED ROYAL PINE DRIVE STORM SEWER AT POWERS RAMP 'D'

H-SCALE: 1"=400'
V-SCALE: N/A

DESIGNED BY: VSF
DRAWN BY: ELY
CHECKED BY: ELY

KETTLE CREEK DRAINAGE BASIN
OLD RANCH ROAD TRIBUTARY
MASTER DEVELOPMENT DRAINAGE PLAN
FULLY DEVELOPED CONDITION
BASIN MAP AND MASTER PLAN

SHEET 1 OF 1
JOB NO. 28877.10